City of Albany

Chevrolet Silverado 3500 Specifications

	2015 Chevrolet Silverado 3500HD Built 4WD
CK36003	Regular Cab 137.5" WB, 59.06" CA WT
01U	Special Paint
1WT	Work Truck Preferred Equipment Group
9W3	Paints, solid, Wheatland Yellow
A31	Windows, Power
AE7	Seats, Front 40/20/40 Split-Bench
AQQ	Remote Keyless Entry
DD8	Mirror, Inside Rearview Auto-Dimming
	Mirrors, Outside Heated Power-Adjustable Vertical
DPN	Camper, Upper Glass, Manual Fold
GT5	Rear Axle, 4.10 Ratio
H2Q	Dark Ash, Vinyl
IO3	Audio System, 4.2" Diagonal Color Display AM/FM
JL1	Trailer Brake Controller, Integrated
K4B	Battery, 730 Col-Cranking AMPS, Auxiliary
KW5	Alternator, 220 Amps
L96	Engine, Vortec 6.0L Variable Valve Timing V8 SFI
MYD	Transmission, 6 Speed Automatic, Heavy Duty
NE1	Emissions
NZZ	Underbody Shield
PCR	WT Convenience Package
QZT	Tires, LT235/80R17E All-Terrain
R9Y	Fleet Free Maintenance Not Included
SKP	Wheel, 17"x6.5" (43.2 CM x 16.5 CM) Full-Size, Steel
TGK	Special Paint, Solid, One Color
TRW	Provision for Cab Roof-Mounted Lamp/Beacon
VK3	License Plate Kit, Front
VXH	LPO, Assist Steps, Chromed Tubular, 6" Rectangular
VYU	Snow Plow Prep Package
ZZT	Tire, Spare LT235/80R17E All-Terrain

All 10 Gauge Construction

3" Structural Steel Cross Members on 12" Centers

5" Structural Steel Long Sills

Vertical Braces, sides and tailgate
1/4 CAB Shield with Screen Window
Boxed Top Rails
Single Handle Tailgate Release

Scissors Type Hoist - Electric/Hydraulic-Double Acting
Approx. Capacity 11 Ton
Painted and Installed
Western: 8' Stainless Hopper Spreader 2 YD
Pintle & Ball Combo
Trailer Plug
Back-Up Alarm
Back-Up Light
Fisher 9' Steel Straight Blade Snow Plow Installed (Shoe Kit, Rubber Snow Deflector, and Cutting Edge Additional Upon Request)
Pinnacle Mini Lightbar (EPL7000), Permanent Mount and 12 ft. cord - Clear Dome, Amber LEDs

10,000 lbs. maximum GVWR for vehicle